BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT35733

APPROVED SCHEDULE - B

STP/BBMP/E-PMT/03/2019-20, Date: 14.05.2019

Improvements to drains of 5th Cross road of Shabarinagara in Byatarayanapura in ward no.07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SAMBASHIVA REDDY C ( )	
				In Figures	In Words
1	290.41	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.	Cum	126.5	Rupees One Hundred Twenty Six and Fifty Paise Only
2	47.6	Providing and laying in position plain cement concrete of nominal mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification .	Cum	4964.65	Rupees Four Thousand Nine Hundred Sixty Four and Sixty Five Paise Only
3	92.69	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.460 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications. Seocifications No. KBS 4.1,4.6	Cum	5506.65	Rupees Five Thousand Five Hundred Six and Sixty Five Paise Only
4	5.1	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	Sqm	69055.59	Rupees Sixty Nine Thousand Fifty Five and Fifty Nine Paise Only
5	601.2	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	Sqm	443.72	Rupees Four Hundred Forty Three and Seventy Two Paise Only
6	301.32	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	1927.8	Rupees One Thousand Nine Hundred Twenty Seven and Eighty Paise Only
7	6	Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications. MORTH Specification No. 2900 B. 1200 mm dia MORTH Specification No. 1000,2300	m	5486.22	Rupees Five Thousand Four Hundred Eighty Six and Twenty Two Paise Only
8	0.68	Providing 100mm and down size nominal size	cum	906.63	Rupees Nine Hundred Six and Sixty Three Paise Only
9	0.45	Providing 40mm and down size nominal size	cum	1001.93	Rupees One Thousand One and Ninety Three Paise Only
10	0.45	Providing 20mm and down size nominal size	cum	1001.93	Rupees One Thousand One and Ninety Three Paise Only

C. Sambashiva Reddy
Signature of the contractor

26/06
Executive Engineer
26/06

	oved Qty.	Description	Unit	Approved Tender Rates of SAMBASHIVA REDDY C ( )	
				In Figures	In Words
	0.34	Providing Fine aggrgate 2.36mm nominal size	cum	967.83	Rupees Nine Hundred Sixty Seven and Eighty Three Paise Only
12	75	Providing and fixing MS Grating 260x260 mm	nos	77.8	Rupees Seventy Seven and Eighty Paise Only
13	290.41	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1	cum	86.6	Rupees Eighty Six and Sixty Paise Only

C. Samba Shiva Reddy
Signature of the Contractor

26/06
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/06